



**City of Pompano Beach, Purchasing Division
1190 N.E. 3rd Avenue, Building C
Pompano Beach, Florida, 33060**

August 10, 2015

ADDENDUM #8, BID T-35-15

MLK BOULEVARD STREETScape PROJECT (LOCAL AGENCY PROGRAM-LAP)

To Whom It May Concern,

Please review the questions submitted by potential bidders, and answers from the City.

Q1: Please clarify the irrigation backflow size, typically the backflow size is the same as the main line. Currently the backflow is shown to be a 2 ½" while the irrigation main is 3".

A1: The irrigation design consultant analyzed the system pressure and found that the loss through a 2-1/2" Backflow Preventer was the same as for a 3". The installation of a 3" is an acceptable alternative.

Q2: What fees for the irrigation meter will the GC be responsible for?

A2: Contractor is responsible for all fees. See Addendum # 6.

Q3: Main line is scheduled to have mechanical joint fittings, what type of mechanical joint fittings will be acceptable?

A3: Mechanical joint fittings (used in water main construction) typically begin for mains 4" and larger. There are however manufacturers including Leemco and Harco that make the mechanical joint fittings for irrigation (starting at 2" diameter on up). Use of the solvent weld fittings for the 3" main is to be considered if allowed by the municipality. Otherwise, please provide Gasketed Mechanical Joint fittings. The irrigation design consultant recommends HARCO.

Q4: Will the City allow International Experience of Similar/equal standards?

A4: The City does not object.

Q5: Is staging area provided by the City?

A5: No. Contractor to manage. The City will assist, if necessary.

Q6: On the item description sheet we don't see conduit, wiring or pull box quantities. Do we need to

make our own take-off for these items or are we supposed to receive quantities as per all the other items given?

A6: Per Addendum #6, Plans to be used for bidding purposes shall be per MLK BLVD-DELTA 7 REV 7-21-2015 –COMPLETE.

Q7: On page 19 of the item description sheets there is an Alternative A1 showing 8 each of Type SA light fixtures/ poles and an Alternative A2 showing 23 each of Type SB light fixtures/ poles. Are these 2 alternatives included in the 34 poles that the plan show? They would be 3 short.

A7: Per Addendum #6, Plans to be used for bidding purposes shall be per MLK BLVD-DELTA 7 REV 7-21-2015 –COMPLETE.

Q8: What would be the breakdown for conduit, wire, pull boxes, service points for each alternative?


Also the quantity for each type of pole is different in the plans than that of the alternatives given.

A8: Per Addendum #6, Plans to be used for bidding purposes shall be per MLK BLVD-DELTA 7 REV 7-21-2015 –COMPLETE.

The deadline for acceptance of sealed bids in the Purchasing Office, 1190 N.E. 3rd Avenue, Bldg. C, Pompano Beach, 33060, is **2:00 p.m. (local), August 13, 2015.**

The remainder of the solicitation is unchanged at this time. Acknowledge receipt of this Addendum in the area provided on Page 14 of the bid.

Sincerely,



Jeff English
Purchasing Agent

cc: website
file